


Cost and Schedule

Ron Strykowski

**NSTX Upgrade Project
Conceptual Design Review
LSB, B318
October 28-29, 2009**

College W&M
Colorado Sch Mines
Columbia U
CompX
General Atomics
INEL
Johns Hopkins U
LANL
LLNL
Lodestar
MIT
Nova Photonics
New York U
Old Dominion U
ORNL
PPPL
PSI
Princeton U
Purdue U
SNL
Think Tank, Inc.
UC Davis
UC Irvine
UCLA
UCSD
U Colorado
U Illinois
U Maryland
U Rochester
U Washington
U Wisconsin



Culham Sci Ctr
U St. Andrews
York U
Chubu U
Fukui U
Hiroshima U
Hyogo U
Kyoto U
Kyushu U
Kyushu Tokai U
NIFS
Niigata U
U Tokyo
JAEA
Hebrew U
Ioffe Inst
RRC Kurchatov Inst
TRINITI
KBSI
KAIST
POSTECH
ASIPP
ENEA, Frascati
CEA, Cadarache
IPP, Jülich
IPP, Garching
ASCR, Czech Rep
U Quebec

Topics

- **Basis of Estimate**
- **Results**
(Cost, funding requirements, schedule, staffing)
- **Plans forward**
- **Conclusion**
(Address charge questions)

Estimate Formulation based on a disciplined process

- Job Managers Prepared Work Authorization Forms (WAF's) - realistic “center-of-errors bars” estimate

Disciplined and uniform approach for all work

Excel based spreadsheet includes;

Tab A – Work scope description

Tab B – Detail estimate; Tasks, resource estimates (labor hours by skill and material cost), schedule and task durations, basis of estimates

Tab C – Estimate uncertainty and Risk

Estimate Uncertainty – Design maturity and complexity

Risk – Likelihood, cost and schedule impact

Tab D – Materials, hardware detail and other backup estimate basis

- Internal Engineering Department Review for all Job Estimates
- Prepared resource Loaded Schedule (Primavera)
1457 tasks, 1751 links, 2259 individual resource loadings
- Quantified Contingency by considering the estimate uncertainty (design complexity and design maturity) and Risk

- ***The WAF's are the basis of all estimates***
- ***Risks were entered into the project risk registry and used to quantify contingency***
- ***Estimate uncertainty was used to quantify contingency***
- ***The resource loaded schedule is the master schedule and cost estimate data base***

Project Scope (WBS) provides basis for estimating and managing

Project WBS

WBS	WAF (Detail of Estimate)	Responsible Job Manager	WBS	WAF (Detail of Estimate)	Responsible Job Manager
1.1 Torus Systems			1.3 Auxiliary Systems		
1000 CSU Analytical Support		P. Titus	1.3.1 Vacuum Pumping Systems		
1.1.1 Plasma Facing Components			2485 Vacuum Pumping Systems		Priniski
1001 CS- PLASMA FACING COMPONENTS		K. Tresemer	1.3.2 Coolant Systems		
1002 Passive Plate Analysis and Upgrade Activities		P. Titus	3200 Water Cooling System Mods for CSU		M. Denault
1.1.2 Vacuum Vessel & Support Structure			1.3.3 Bakeout System		
1200 CSU STRUCTURAL SUPPORTS		D. Mangra	3300 Bakeout System mods for CSU		S. Raki
1.1.3 Magnet Systems			1.3.4 Gas Delivery Systems		
1300 CENTER STACK DESIGN SUPPORT		J. Chrzanowski	3400 Gas Delivery System Mods for CSU		W. Blanchard
1.1.3.1 Outer Poloidal Field Coils			1.3.5 Glow Discharge Cleaning System		n/a
1.1.3.2 Outer Toroidal Field Coils			1.4 Plasma Diagnostics		
1301 Outer TF Coil Repairs		J. Chrzanowski	4100 Center Stack Diagnostics for CSU		R. Kaita
1.1.3.3 Center Stack			1.5 Power Systems		
1302 CENTER STACK ASSEMBLY		J. Chrzanowski	5000 CS Power Systems		Raki
1.1.3.3.1 TF Inner legs			5501 COIL BUS RUNS		J. Chrzanowski
1303 TF Joint Test Stand & Performance of Test		T. Kozub	1.6 Central Instrumentation & Control		
1304 INNER TF BUNDLE- Design & Fabrication		J. Chrzanowski	6100 Control System & Data Acquisition System		P. Sichta
1.1.3.3.2 Ohmic Heating Solenoid			1.7 Project Support & Integration		
1305 OHMIC HEATING COIL (OH)		J. Chrzanowski	7100 Project Management & Integration		E.Perry
1.1.3.3.3 Shaping Coils			7200 Center Stack Management		L.Dudek
1306 Inner POLOIDAL FIELD COILS (IPF)		J. Chrzanowski	7300 NB2 Management		T.Stevenson
1.1.3.3.4 Center Stack Casing			7400 Health Physics Support		T.Stevenson
1307 CS CASING Assembly- Design & Fabrication		J. Chrzanowski	7700 Direct Allocations		R.Strykowski
1.2 Plasma Heating and Current Drive Systems			7710 Upgrade Allocations		R.Strykowski
1.2.1 High Harmonic Fast Wave		n/a	7900 Integrated Systems Test		C. Gentile
1.2.2 Coaxial Helicity Injection Current Drive		n/a	1.8 Site Preparation and Torus Assembly		
1.2.3 Electron Cyclotron Heating		n/a	8200 Centerstack and Coil structure Installation		M. Viola
2300 ECH		P. Titus	8250 Centerstack removal & re-installation		M. Viola
1.2.4 Neutral Beam Injection					
2420 NBI - Sources		Cropper			
2425 NBI - Beamline Relocation		Denault			
2430 NBI - Decontamination		T. Stevenson			
2440 NBI - Beamline Refurbishment		Denault			
2450 NBI - Services		Denault			
2460 NBI - Armor/Protective Plates		Priniski			
2470 NBI - Power		Raki			
2475 NBI - Controls		Cropper			
2480 NBI - Nozzle/Duct		Priniski			
2490 NBI - Equipment Relocations		E. Perry			

Key Planning Basis and Assumptions

- TPC - from January 1st, 2009
- Institutional Overhead and Labor Rates
- Standard work week 8hrs/day 5 days/ week
- No overtime or Saturday work planned. Overtime and Saturday used to maintain schedule.
- Holidays included
- Task durations based on deliverables and/or tasks identified by the job managers
- Established tasks, internal milestones (PDR's, FDR's, contract awards)
- Task durations based on realistic resource loadings & crew sizes

Contingency Methodology Recognizes Uncertainty & Risk

- **Lower Range**

- Average range of estimate uncertainty ⁽¹⁾ (%) x base estimate (\$)
- +
- Risk Cost (\$) x likelihood (*weighted*) (%)
- +
- Schedule contingency (critical path tasks average uncertainty (%) x total schedule length (mos.) x standing army cost (\$/mo.)

- **Upper Range**

- High estimate uncertainty ⁽¹⁾ (%) x base estimate (\$)
- +
- Risk Cost (\$) (*not weighted*)
- +
- Schedule contingency (critical path tasks average uncertainty (%) x total schedule length (mos.) x standing army cost (\$/mo.)

(1) Estimate uncertainty consistent with AACE cost estimate classification system

Summary Cost Profile

TPC (\$K)

No Operations

Base Case	FY2009	FY2010	FY2011	FY2012	FY2013	FY2014	FY2015	TOTAL
Base Estimate	\$5,146	\$10,690	\$13,103	\$28,302	\$10,725	\$237		\$68,204
Lower Contingency		\$340	\$1,359	\$2,038	\$1,359	\$1,699		\$6,794
Total Lower Bound	\$5,146	\$11,030	\$14,462	\$30,341	\$12,084	\$1,936		\$74,998
Upper Contingency		\$1,139	\$4,555	\$6,833	\$4,555	\$5,694		\$22,777
Total Upper Bound	\$5,146	\$11,829	\$17,659	\$35,136	\$15,281	\$5,931		\$90,981

No Operations

Constrained Case	FY2009	FY2010	FY2011	FY2012	FY2013	FY2014	FY2015	TOTAL
Base Estimate	\$5,146	\$9,879	\$7,898	\$9,985	\$25,840	\$12,964	\$17	\$71,728
Lower Contingency		\$148	\$520	\$1,485	\$1,485	\$2,227	\$1,559	\$7,424
Total Lower Bound	\$5,146	\$10,027	\$8,417	\$11,470	\$27,325	\$15,191	\$1,576	\$79,152
Upper Contingency		\$483	\$1,690	\$4,828	\$4,828	\$7,243	\$5,070	\$24,142
Total Upper Bound	\$5,146	\$10,362	\$9,587	\$14,814	\$30,668	\$20,206	\$5,087	\$95,870

Anticipated Guidance **\$5,146** **\$8,000** **\$8,440** **\$11,880** **\$28,670** **\$29,060** **\$7,840**

Note: Anticipated guidance for the total NSTX Program distributed amongst program elements by PPPL.

Base Cost Estimate Detail (TPC \$K)

(Base Case)

WBS/JOB	TOTAL BASE	Uncertainty %		Risk		Contingency		ESTIMATE RANGE	
		Low	High	Gross risk \$	Likelihood	Lower	Upper	LOWER	UPPER
Job: 1000 - CSU Analytical Support	\$238	-20%	40%	50	U	\$36	\$145	\$275	\$383
Job: 1001 - CS Plasma Facing Components	\$1,842	-20%	40%	-		\$178	\$711	\$2,020	\$2,553
Job: 1002 -Passive Plate Analysis & Upgrade Act	\$173	-20%	40%	?		\$17	\$69	\$191	\$242
Job: 1200 - Vacuum Vessel & Structural Support	\$776	-20%	40%	-		\$20	\$82	\$796	\$858
Job: 1201 - Outer TF Structures	\$689	-20%	40%	-		\$69	\$275	\$758	\$964
Job: 1202 - Outer PF Coil Structures	\$1,111	-20%	40%	-		\$111	\$444	\$1,222	\$1,555
Job: 1203 - Umbrella Structural Reinforcement	\$397	-20%	40%	-		\$40	\$159	\$437	\$556
Job: 1204 - CS Support Pedestal	\$197	-20%	40%	-		\$20	\$79	\$217	\$276
Job: 1205 - Misc VV Structural Support	\$252	-20%	40%	-		\$25	\$101	\$277	\$352
Job: 1301 - Outer Toroidal Field Coils	\$671	-10%	15%	240	U	\$77	\$341	\$748	\$1,011
Job: 1303 - TF Joint Test Stand & Perform Test	\$341	-15%	25%	75	U	\$36	\$160	\$376	\$501
Job: 1304 - Inner TF Bundle (Dsgn/Fab)	\$1,948	-20%	40%	165	U	\$236	\$944	\$2,184	\$2,892
Job: 1305 - OHMIC Heating Coil (OH) DSGN/FAB	\$3,993	-20%	40%	750	U	\$481	\$1,925	\$4,475	\$5,918
Job: 1306 - Inner Poloidal Field Coils (Shaping)	\$534	-20%	40%	50	U	\$66	\$264	\$600	\$798
Job: 1307 - CS Casing Assembly (DSGN/FAB)	\$875	-20%	40%	-		\$88	\$350	\$963	\$1,225
Job: 1302 - Center Stack Assembly	\$812	-20%	40%	n/a		\$81	\$325	\$893	\$1,137
Job: 2300 ECH Analysis	\$131	-20%	40%	-		\$13	\$52	\$144	\$183
Job: 2420 - 2nd NBI Sources	\$1,309	-5%	10%	-		\$33	\$131	\$1,342	\$1,440
Job: 2425 - BL Relocation	\$1,712	-15%	25%	-		\$85	\$424	\$1,797	\$2,137
Job: 2430 - 2nd NBI Decontamination	\$2,640	-20%	10%	-		-\$70	\$140	\$2,570	\$2,780
Job: 2440 - 2nd NBI Beamline	\$2,378	-10%	15%	(184)	L	-\$52	\$168	\$2,326	\$2,546
Job: 2450 - 2nd NBI Services	\$3,542	-15%	25%	50	U	\$186	\$916	\$3,728	\$4,459
Job: 2460 - 2nd NBI Armor	\$424	-10%	15%	-		\$10	\$58	\$433	\$482
Job: 2470 - 2nd NBI Power	\$2,829	-15%	25%	50	U	\$148	\$729	\$2,978	\$3,558
Job: 2475 - 2nd NBI Controls	\$1,691	-15%	25%	-		\$85	\$423	\$1,775	\$2,113
Job: 2480 - 2nd NBI/TVPS Duct	\$2,457	-10%	15%	170	U	\$99	\$511	\$2,556	\$2,968
Job: 2485 - Vacuum Pumping System	\$314	-5%	10%	-		\$8	\$31	\$321	\$345
Job: 2490 - NTC Equipt Relocations	\$3,241	-20%	40%	441	L	\$574	\$1,680	\$3,815	\$4,921
Job: 3200 - Water Cooling System Mods for CSU	\$382	-15%	25%	-		\$19	\$94	\$400	\$476
Job: 3300 - Bakeout System Mods for CSU	\$80	-5%	10%	-		\$2	\$8	\$82	\$88
Job: 3400 - Gas Delivery System Mods for CSU	\$88	-15%	25%	-		\$4	\$22	\$92	\$110
Job: 4100 - Center Stack Diagnostics for CSU	\$849	-5%	10%	-		\$21	\$84	\$870	\$933
Job: 5000 - CSU Power Systems	\$8,767	-15%	25%	-		\$419	\$2,095	\$9,186	\$10,862
Job: 5501 - Coil Bus Runs	\$702	-20%	40%	-		\$70	\$281	\$773	\$983
Job: 6100 - Control Sys & Data Acquisition Sys	\$781	-15%	25%	250	U	\$102	\$445	\$883	\$1,226
Job: 7100 - Project Mgt & Integration CSU & NBI	\$4,221	-15%	25%	-		\$180	\$899	\$4,401	\$5,120
Job: 7200 - Center Stack Management	\$1,327	-15%	25%	107	L	\$131	\$439	\$1,458	\$1,766
Job: 7300 - NB2 Management	\$1,582	-15%	25%	75	L	\$121	\$455	\$1,703	\$2,036
Job: 7400 - Health Physics Support	\$2,838	-15%	25%	35	L	\$163	\$745	\$3,001	\$3,583
JOB: 7700 - NSTX Upgrade HP Allocations	\$1,836	-15%	25%	130	L	\$170	\$589	\$2,006	\$2,425
Job: 7710 - Upgrade Allocations	\$918	-15%	25%	130	L	\$98	\$228	\$1,016	\$1,146
Job: 8200 - Centerstack & Coil Structural Instal	\$5,499	-20%	40%	50	U	\$562	\$2,250	\$6,062	\$7,749
Job: 8250 - Remove/Install Centerstack	\$749	-30%	60%	287	L	\$284	\$736	\$1,033	\$1,485
Job: 7900 - Integrated System	\$69	-20%	40%	-		\$7	\$28	\$76	\$96
schedule (months)	48		7.2			\$1,742	\$1,742	\$1,742	\$1,742
Base Estimate =	\$68,204			2,921		\$6,794	\$22,777	\$74,998	\$90,981
						10%	33%		

•Base Estimate = \$68.2M

•Contingency range 10% - 33%

•TPC range \$75M - \$91M

•Schedule Contingency 7.2months

Cost and Schedule Opportunities

The project is currently pursuing potential reductions to the base estimate.


1) Simplification and optimization of the coil support structures.

The current proposed design assumes an over powering of the TF and PF coils scenario which would require significant structural bracing to confine the coils. The addition of the Machine Protection System (MPS) would control and limit power to the coils which would negate the need for such a robust structure. Savings would result from reduced material cost AND significantly less ancillary hardware removals and re-installations. Estimate cost savings \$1.6M


2) Hardware Installation.

Further review of the assembly plan reveals potential optimization of steps required and labor reductions. Estimated savings \$0.6M


Project Funding Requirements



Project Staffing Requirements



Project Schedule (Base Case)



Major Procurements

(Procurements > \$100,000)

<u>Job:</u>	<u>Description</u>	<u>Award/Begin Work</u>		<u>Amount</u>
Job: 1304 - Inner TF Bundle (Dsgn/Fab)	Manufacture Inner TF Copper extrusions [80]	FY10	15-Mar-10	\$ 242,000
Job: 1304 - Inner TF Bundle (Dsgn/Fab)	Machine Inner TF conductors [grooves, lead area]	FY10	21-Jul-10	\$ 250,000
Job: 1305 - OHMIC Heating Coil (OH) DSGN/FAB	Manufacture OH Copper conductor [extrusion]	FY11	08-Oct-10	\$ 105,600
Job: 1304 - Inner TF Bundle (Dsgn/Fab)	Friction Stir-Weld coil leads conductors- 40	FY11	21-Oct-10	\$ 250,000
Job: 1305 - OHMIC Heating Coil (OH) DSGN/FAB	Fabricate Inner TF/OH Coil Assembly	FY11	31-Mar-11	\$ 1,972,600
Job: 2450 - 2nd NBI Services	Ion Dump Water Lines	FY11	01-Jul-11	\$ 135,000
Job: 5000 - CSU Power Systems	531- FCPC DC Systems -Procure 1000MCM Cable & Tr	FY11	10-Aug-11	\$ 143,000
Job: 5000 - CSU Power Systems	531- FCPC DC Systems -Procure OH Reactors	FY11	10-Aug-11	\$ 100,000
Job: 1201 - Outer TF Structures	Fabricate Outer TF Structure components	FY11	15-Aug-11	\$ 297,600
Job: 1306 - Inner Poloidal Field Coils (Shaping)	Fabricate Inner [6] Inner PF coils	FY11	19-Aug-11	\$ 180,000
Job: 1001 - CS Plasma Facing Components	Fabricate or delivery - PFC Tiles	FY11	30-Aug-11	\$ 650,000
Job: 1001 - CS Plasma Facing Components	Fab or delivery PFC Hardware & Materials	FY12	03-Oct-11	\$ 150,000
Job: 5000 - CSU Power Systems	541 - Electrical Interlocks -Procurement PLC	FY12	03-Oct-11	\$ 102,000
Job: 5000 - CSU Power Systems	544 -PC Link/FD/FG changes -Procure control link	FY12	03-Oct-11	\$ 830,000
Job: 5000 - CSU Power Systems	545 - Instrumentation -Procure Transducers	FY12	03-Oct-11	\$ 229,000
Job: 5000 - CSU Power Systems	MPS -Procurement	FY12	03-Oct-11	\$ 298,000
Job: 2480 - 2nd NBI/TVPS Duct	Fabricate / Delivery - NBI RWM Coil	FY12	05-Oct-11	\$ 170,000
Job: 2475 - 2nd NBI Controls	Fabricate or delivery 2nd NBI Controls	FY12	18-Oct-11	\$ 312,000
Job: 1202 - Outer PF Coil Structures	Fabricate Outer PF Cage [PF-3/4/5]	FY12	08-Nov-11	\$ 350,000
Job: 1202 - Outer PF Coil Structures	Fabricate PF-2/PF-1c support modifications	FY12	09-Nov-11	\$ 118,800
Job: 2480 - 2nd NBI/TVPS Duct	Fabricate / Delivery - NBI 40" VAT Valves (2)	FY12	11-Nov-11	\$ 250,000
Job: 2450 - 2nd NBI Services	HVE Water Lines	FY12	15-Nov-11	\$ 100,000
Job: 2480 - 2nd NBI/TVPS Duct	Fabricate / Delivery - NBI 40" Bellows Section	FY12	15-Nov-11	\$ 300,000
Job: 2470 - 2nd NBI Power	Procurement/Fab/Assembly - 2nd NBI Cables	FY12	18-Jan-12	\$ 422,200
Job: 1203 - Umbrella Structural Reinforcement	Fabricate umbrella lids	FY12	19-Jan-12	\$ 100,000
Job: 5000 - CSU Power Systems	531- FCPC DC Systems - Instl cable & misc h/w	FY12	01-May-12	\$ 535,000
Job: 2470 - 2nd NBI Power	Installation - 2nd NBI Raceway	FY12	09-Aug-12	\$ 480,000

- **Center stack Hardware**
- **On or near critical path**
- **Required before CD-3 (April 2011)**

Management Process

The NSTX Upgrade project will be managed using PPPL's cost and schedule control processes

(Project Management System Program Description (PMSPD) Revision 0 July 2009)

- **Adopt the conceptual design plan as our baseline through preliminary design (CD-2) (will adjust in response to CDR and OFES findings)**
- **Monthly progress measurement including;**
 - **Earned value**
 - **Risk registry review**
 - **EAC assessment**
- **Monthly reporting including**
 - **Status barcharts**
 - **Cost performance reports (CPR's) including EAC's**
 - **Updated risk registry**
- **Change control process – changes documented via engineering change proposals (ECP's)**

Conclusions

- **Is the proposed cost range adequate for CD-1?**

- *The conceptual design estimate was prepared following a disciplined process and is credible for this stage of the project.*
- *The work scope is complete, well organized with clear assignment of responsibilities.*
- *A well detailed resource loaded schedule exists and provides the basis for all cost and schedule estimates.*
- *The contingency and methodology used to established the upper and lower cost range is reasonable for this stage of the project.*

- **Is the proposed schedule realistic for CD-1?**

- *The schedule is realistic and achievable based on the resource availability and level of schedule detail.*

- **Is the project organization/staffing appropriate?**

- *Staffing requirements have been clearly defined and are achievable.*
- *The project is currently staffed to begin the preliminary design phase.*
- *The project has been responsive in addressing both programmatic mission goals (base case) as well as anticipated funding guidance (constrained case).*
- *The project is poised to initiate and effectively manage the preliminary design phase of the project.*