


Coil Support Structures

College W&M Colorado Sch Mines Columbia U CompX **General Atomics** INEL Johns Hopkins U LANL LLNL Lodestar MIT **Nova Photonics** New York U **Old Dominion U ORNL** PPPL PSI Princeton U Purdue U SNL Think Tank, Inc. **UC Davis UC Irvine** UCLA UCSD **U** Colorado

Design by D. Mangra Presented by L. Dudek

NSTX Upgrade Project Conceptual Design Review LSB, B318 October 28-29, 2009





York U Chubu U Fukui U Hiroshima U Hyogo U Kyoto U Kyushu U Kyushu Tokai U Niigata U **U Tokyo JAEA** Hebrew U loffe Inst **RRC Kurchatov Inst** TRINITI **KBSI** KAIST **POSTECH ASIPP** ENEA, Frascati CEA, Cadarache IPP. Jülich IPP, Garching ASCR, Czech Rep **U** Quebec

Culham Sci Ctr

U St. Andrews

U Illinois

U Maryland

U Rochester

U Wisconsin

U Washington

Outline

- Tasks
- Scope / Requirements / Standards
- Existing Structure
- Design Approach
- Issues
- Summary



Structural- Design

Scope:

- Structural Support Components
 - Support Coils: TF, PF2, PF3, PF4 and PF5
 - Support Pedestal: To Support new Center Stack
 - Umbrella structure reinforcement to carry higher magnetic loads

Requirements:

- Resist Forcing Inputs
- Interface with Legacy equipment
- Real Estate available for installation
- Coil Alignment ~5 mm

Standards:

- Stress in house design standard
- Installation and handling Module Size and weight such that parts can be easily handled and installed
- Minimize the impact to existing hardware
- Minimize the impact to existing assembly as installed




Force Inputs

Cage Links	Power Supply Limit		Operational Limit	
	Max (lbs)	Min (lbs)	Max (lbs)	Min (lbs)
PF 3 Upr to PF 4 Upr Link	272,631	-314,951	103,217	-150,417
PF 5 Upr to PF 5 Lwr Link	665,724	-666,010	258,062	-239,821
PF 4 Lwr to PF 3 Lwr Link	116,805	-471,392	35,711	-150,441
Upper dome load	194,759	-369,644	59,209	-59,365
Lower dome load	191,694	-194,844	44,531	-59,250
Load by vessel to 4 legs to ground	495,107	-495,329	58,722	-65,529




Existing TF & PF Support Details and integration






New Supports Designed to use same Real Estate as Existing






NSTX Main Assembly with PF Cage Support




TF Coils and Supports upgrade






TF Tangential Support Details






Umbrella Reinforcement






Pedestal Assembly






PF Coil Support Assembly

Item # in order of installation






PF Cage – Coils Assembly with bottom support






PF Cage Stabilizer





PF Cage to Floor Connection





Installation Procedure Plan

- Install (TBD) Shaping fixtures to PF5
- Remove existing coil clamps on PF5 and PF4
- Upper PF5/PF4 are raised & Lower PF5/PF4 are lowered
- Inspect coils for repairs (leaks etc) & repair if needed
- Reposition upper PF5 & install PF5 cage clamps
- Link PF4 to PF5 via mechanical supports
- Add columns to PF5 and repositioned lower PF5
- Process continued on the lower coils
- Each coil is mechanical aligned for concentricity
- Leg system for the cage is attached
- Alignment system relative to legs of vessel is installed
- Cage system can be slid on ground (grouting plate to be designed)
- Align cage and bolt to ground/grouted plate
- Remove shaping fixture & alignment fixture
- Address electrical isolation/grounding needs



Issues

- PF2 Coil Support Structure not yet started however the support should be straightforward
- Vessel stands
 - The launching loads on the vessel exceed the capability of the existing vessel connections so some reinforcement will need to be implemented
- Cage Support
 - Still evolving and being evaluated against all of the operational scenarios



Impacts

- Ribs on vessel need significant modification insitu
- Clevises on vessel must be removed and replaced with stronger versions
- Column Supports are installed inside the Outer TFs in 12 locations. Optimization may allow reductions.
- Additional supports for PF cage to the floor



SUMMARY

Concept Matured:

- PF3, PF4 and PF5 (upper and Lower) support structure
- TF coils(12) support structure
- Pedestal for center Stack
- Both PF and TF coil supports are compatible with the NB2 Bay J/K modifications

Concept Pending:

- PF2 coils
- Umbrella structure leg reinforcement

Issues- Real estate

- Difficulty to install the upgraded structure needs to be evaluated
- Optimization is expected to identify opportunities for simplifications and cost savings

