

Supported by



OH Coil Design Description

Coll of Wm & Mary Columbia U CompX **General Atomics** FIU INL Johns Hopkins U LANL LLNL Lodestar MIT Lehigh U **Nova Photonics** ORNL PPPL **Princeton U** Purdue U SNL Think Tank, Inc. UC Davis UC Irvine UCLA UCSD **U** Colorado **U Illinois** U Maryland U Rochester **U** Tennessee **U** Tulsa U Washington U Wisconsin X Science LLC

L. Dudek

and the NSTXU Engineering Team

OH Circuit Fault External Review B318 5/28/2015



Culham Sci Ctr York U Chubu U Fukui U Hiroshima U Hyogo U Kyoto U Kyushu U Kyushu Tokai U NIFS Niigata U **U** Tokyo JAEA Inst for Nucl Res, Kiev loffe Inst TRINITI Chonbuk Natl U NFRI KAIST POSTECH Seoul Natl U ASIPP CIEMAT FOM Inst DIFFER ENEA. Frascati CEA, Cadarache **IPP, Jülich IPP, Garching** ASCR, Czech Rep

OH Solenoid Parameters



🔘 NSTX-U

OH Solenoid Materials

- Conductor : C10700 –Oxygen free-silver bearing copper conductor Insulation:
 - Turn Insulation: Co-wound Kapton/S2 glass tape
 - Ground wrap Insulation: Half-lapped layers- 0.006 inch thick S-2 (satin weave) standard silane finish glass tape- (Temperature class- 180 degrees C)
- Fillers: All G-11 laminate material
- **Cooling Fittings:** Custom cast copper components C10200
- VPI System- CTD-425 Cyanate-Ester Hybrid system
 - Cure cycle: 22 hours @ 100 degrees C
 - Post Cure Cycle: 24 hours @ 170 degrees C



Upper OH Coil Arrangement





OH Coil Winding Potentials





OH Layer to Layer Joints



Layer to layer TIG-Braze joint [Typical]

"TIG-Braze"

TIG-Brazing method minimizes annealing of conductors (use Sil-Fos)

Provides adequate joint strength

Qualified method and procedures used in previous OH solenoids



OH Compression Ring

- Purpose to hold OH Coil in place under launching loads and during bakeout thermal expansion
- Consists of a set of six half rings preloaded by belleville springs at the time of installation. Preload is adjustable
- The assembly splits into halves so it can be installed after potting of the OH coil
- Required 14 stacks of 26 bellevilles to maintain a minimum of 20,000 lbs load on the OH.
- This assy was found to be floating electrically.



Upper Water Connections

- Design adopted from NSTX OH Water Connections
- Polypropylene clamps serve double duty as supports and insulators.
- Water tubes are overwrapped with 3 mil Kapton before applying clamp. Assy passed 13kv Hipot test (on the bench).
- Fitting where it enters the coil is left bare to allow inspection for water leakage
- Normally the OH hose connections would be non conductive. The (8) upper an lower hoses are 316SS to meet OH Water Heater requirements.
- The SS hoses are double insulated and terminated just outside the Umbrella in G10 Blocks. Were tested successfully to 17 kv on the bench.
- The SS hoses do not appear to have been involved in the event.





Upper Water Conn



TOP VEW LAYER ' & 2

~



Ground Plane Grounding Clamp

- Grounding clamp is documented on B-4F1005, however it was not updated for NSTXU.
 - Note: "1/2" Wide Braided copper straps insulated on one side"
- Was installed by a machine tech per verbal instructions from electrical engineer. The installation is confirmed in IP-3572.
- Engineer instructed technician to avoid loops.
- Technician interpreted as not connecting ends together as they came around coil





Lower OH Coil Arrangement

Layer-Layer Water Conns Grounded Support Structure **Coaxial OH Connector OH Lead Water Conns**

Lower Water Conn





Lower Water Connections

- At 6 locations, the design utilizes the same polypropylene clamp in the upper connections.
- The 2 connections at the leads coming into the coil are clamped by solid blocks of G10.
- The brackets are welded to the OH support structure which is grounded to the CS casing.
- All of these connections have passed the 9 kv field Hipots without any issues.



OH Lead Box & Water Conns

- OH Features a coaxial input connector to minimize forces between conductors.
- The two leads are brazed to copper flags that are wrapped in Kapton tape and are supported by a G10 enclosure wrapped in a heavy 316SS Box.
- The water connections are also wrapped in Kapton and are separated by a G10 partition at their closest point.



OH Coax Connection

- G10 Insulating tube between inner and outer conductor
- Kapton on exposed copper connector flags
- Outer conductor insulated with Kapton and over wrapped with fiberglas and Hysol RT cure epoxy.
- This assy was hipotted to 13kv on the bench.
- This piece is being reinforced by epoxy injection between G10 and outer conductor to eliminate bending (See Raftopoulos talk)



OH Lead Box Detail

- All metal lead box surfaces that faced conductors were insulated with Kapton.
- Any non-contact surfaces of the OH lead flags were insulated with Kapton
- After installation of the water connections in the field tubes were Kapton wrapped and G10 support blocks were installed.
- The lower OH water connections have hipotted in the field to 9kv.
- SS Hose assembly was hipotted on the bench to 17kv.



Electrical Testing

- Acceptance test in the Coil Winding Facility:
 - 12 microamps @ 13 kV
 - 23 microamps @ 9 kV
- OH installed in NSTX-U. Hi-Potted from the PCTS in the NTC:
 - 27 microamps @ 9 kV
- OH installed in NSTX-U. Hi-Potted from the SDS in FCPC:
 - 42 microamps @ 9 kV





Summary

- The OH Coil is a robust design
- Attention to detail was paid to ensure the conductors are well insulated from each other and in the OH connector box.
- The water fittings in the upper end of the coil are well away from the OH turns making damage to the coil unlikely
- Hipot Testing of individual components was performed at 13 Kv (2E+1) to ensure reliability.
- Since the arc fault the OH coil has been inspected and retested successfully:
 - Cooling Passage connections inspected for damage
 - Hydrotest of cooling channels passed successfully
 - Pneumatic flow test of passages passed
 - Repeated Megger tests have passed for the OH insulation
- All indications are that the OH coil has been undamaged by this event.